

Clearbrook Road / Johnson Creek Bridge #302 - CRP #905017 2010 Annual Construction Program

Construction Funding Year(s): 2010

Project Narrative:

This project is located southwest of the city of Sumas in Section 4, T40N, R5E. This is a federally funded bridge replacement project that involves removal of the existing structurally deficient bridge and replacement with a 50-foot single span prestressed voided slab on steel piles and cast in place concrete abutments. Bridge rails and guardrail approaches will be installed. This project is listed #12 on the 2010–2015 Six Year Transportation Improvement Program.

New Construction Features:

Total Width	32'
Bridge Length	50'
Shoulder Width	N/A
Curb / Gutter	N/A
Sidewalk	N/A

Project Status:

Design & permitting completed. Funding has been obligated. Construction to occur in the spring/summer of 2010.

Project Funding:

	2010	Total
Federal / State	\$800,000 (BR)	\$800,000 (BR)
Local	\$0	\$0
Total	\$800,000 (BR)	\$800,000 (BR)

Environmental Permitting (Agencies/Permits):

HPA, Sec. 404 Clean Water Act, Shorelines, SEPA, CLR/CAO, Sec. 401 Water Quality Certification

Right-of-Way Acquisition (\$ Estimate):

N/A

County Forces (\$ Estimate):

To Be Determined

